F-6-52

Ca. 1830

Harbaugh-Willard Farm

Sabillasville, Maryland

Private

The Harbaugh-Willard Farm is a 2 story brick house with a side gable roofline. The building is significant in representing the architecture of a prosperous nineteenth century farm through the proportions and details of the main house. Although vernacular in rendition, the house was executed with slightly higher standards than seen in its neighbors. This up-scale rendition included an elaborate entrance and the use of flemish bond brick work. The farm is also associated with the Harbaughs, an influential family in the region, which is still referred to as the Harbaugh Valley. Its representative domestic and agricultural outbuildings reveal its association with agriculture.

F-6-52 Harbaugh-Willard Farm Sabillasville Frederick County

### **HISTORIC CONTEXT:**

### MARYLAND COMPREHENSIVE HISTORIC PRESERVATION PLAN DATA

Geographic Organization: Piedmont (Harford, Baltimore, Carroll, Frederick, Howard, Montgomery Counties, and Baltimore City)

Chronological/Development Period:
Agricultural-Industrial Transition 1815-1870
Industrial/Urban Dominance 1870-1930

Prehistoric/Historic Period Themes:
Architecture, Landscape Architecture and Community Planning
Agriculture

## Resource Type:

Category: Buildings

Historic Environment: Rural

Historic Function and Use:
 Domestic/single dwelling/residence
 Domestic/secondary structure/outbuilding
 Agricultural/Subsistence/agricultural outbuilding/barn,
 tractor shed
 Agricultural/Subsistence/animal facility/chicken coop, sheep
 shed

Known Design Source: None

# MARYLAND INVENTORY CT

# Maryland Historical Trust HISTORIC PROPERTY: State Historic Sites Inventory Form

Survey No. F-6-52 Magi No.

DOE \_\_yes \_\_no

			<del></del>	
1. Nam	e (indicate pr	eferred name)		
historic Han	rbaugh-Willard Farm	1		
and/or common				
2. Loca	ation			
street & number	16825-B Sabilla	sville Road		not for publication
city, town Sa	abillasville	vicinity of	congressional district	6th
state Ma	aryland	county	Frederick	
3. Clas	sification			
Category  districtX building(s) structure site object	Ownership public private both Public Acquisition in process being considered not_applicable	Status X occupied unoccupied work in progress Accessible X yes: restricted yes: unrestricted no	Present Use  X agriculture commercial educational entertainment government industrial military	museum park X private residence religious scientific transportation other:
4. Own	er of Prope	<b>rty</b> (give names an	d mailing addresse	s of <u>all</u> owners)
name Glen	K. & Mabel M. Will	ard		
street & number	16825-B Sabillas	ville Road	telephone no	).:
city, town	Sabillasville	state		. 21780
5. Loca	tion of Leg	al Descriptio	n	· · · · · · · · · · · · · · · · · · ·
		derick County Courth		liber 481
street & number	100 West Patrick	Street		folio 357
city, town	Frederick		state	Md.
6. Repr	esentation	in Existing	Historical Surv	eys
titie				
d <b>a</b> te			federai state	e county iocal
pository for su	rvey records			
city, town			state	

Condition	deterioreted	Check one	Check one		
excellent	deteriorated	unaltered	_ <del></del>		
$\underline{X}$ good	ruins	X altered	moved date of move		
fair	unexposed				

Survey No. F-6-52

7. Description

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

8. 5	Sign	ificance	Survey No. F-6-52		
1600	0–1499 0–1599 0–1699 0–1799 0–1899	archeology-historic _X_ agriculture _X_ architecture	community planning	iterature military music muphilosophy politics/government	religion sclence sculpture social/ humanitarian theater transportation other (specify)
Specific	dates		Builder/Architect		
check:	ar	icable Criteria:A nd/or icable Exception:A		EFG	
	Level	l of Significance:	nationalstate _	<u>x</u> local	
Prepare	both	a summary paragraph o	of significance and a	general statement of	history and

## **Major Bibliographical References** F-6-52 Survey No. Atlas of Frederick County, Maryland, C.O. Titus and Co., Philadelphia, 1873 Map of Frederick County, Maryland, Isaac Bond, Baltimore, 1858. Williams, T.J.C. History of Frederick County, Maryland, L.R. Titsworth & Co., Frederick, 1910. **Geographical Data** 191.50 acres Acreage of nominated property Quadrangle name Blue Ridge Summit MD Quadrangle scale 1:24000 **UTM References** do NOT complete UTM references Easting **Northing** Zone Easting Zone Verbal boundary description and justification Tax Map 6 Parcel 59 List all states and counties for properties overlapping state or county boundaries code code county state code county code state Form Prepared By Mary Kendall Shipe, Historic Sites Surveyor name/title Frederick County Planning & Zoning Dept. date May, 1991 organization 12 E. Church Street 696-2958 telephone street & number Frederick Md. 21701 state city or town The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated

Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to:

Maryland Historical Trust

Shaw House 21 State Circle

Annapolis, Maryland 21401

(301) 269-2438

### 7.1 Description

The Harbaugh-Willard Farm is a 2 story brick house with a side gable roofline located approximately 1/4 miles to the southeast of Sabillasville, Maryland. The principal elevation faces west and contains 3 bays. The farm includes a collection of domestic and agricultural outbuildings.

Resting on a stone foundation, the house consists of flemish bond brickwork on the principal facade and 5 course common bond on the other Its side gable roof of standing seam tin contains one interior elevations. On the west facade, 6/6 light windows are symmetrically brick end chimney. placed on both floors. The side door placement on the first floor contains an elaborate entrance with a fanlight, sidelights and pilasters surrounding a A one story hipped roof open porch covers the full facade and panelled door. has turned columns and carved brackets. A 2 story brick ell addition extends from the east elevation; it contains 5 course common bond brickwork. Its gable roof of composition shingling intersects with the main house gable and contains an interior brick end chimney. The elevation contains 6/6 light windows on the first and second floors and 4 light fixed attic windows. A brick shed addition projects off the brick section and has a shed roofed frame entry hood into the cellar.

The north elevation has symmetrical fenestration with 6/6 light windows in both the main block and the addition. The main block has splayed lintels consisting of 3 stacked soldier courses on the first floor and jack arches on the second. The attic has 4 light fixed windows. The gable end has an incomplete cornice return. The cornice is corbelled. The south elevation has no openings in the main block except for 4 light fixed attic windows. The ell addition is recessed in the center creating a 2 story porch which has been enclosed and sheathed in asphalt shingling. The rest of the ell is flush with the enclosed porch section; it has 6/6 and 1/1 light windows. The brick shed roofed attachment contains a door opening.

Three domestic outbuildings are located within the yard surrounding the house including an frame octagonal chicken coop with 6/6 light windows, a sheep shed with tongue and groove siding, and a one story aluminum sided cottage. Agricultural outbuildings further from the house include a new metal barn with a silo, a gambrel roofed concrete barn and a tractor shed. These buildings are still utilized for agricultural pursuits. A modern rancher house is located several yards from the main house.


## 8.1 Significance


The Harbaugh-Willard Farm is significant in representing the architecture of a prosperous nineteenth century farm through the proportions and details of the main house. Although vernacular in rendition, the house was executed with slightly higher standards than seen in its neighbors. This up-scale rendition included an elaborate entrance and the use of flemish bond brick work. The farm is also associated with the Harbaughs, an influential family in the region, which is still referred to as the Harbaugh Valley. Its representative domestic and agricultural outbuildings reveal its association with agriculture.

Considered in its historic context, the Harbaugh-Willard Farm contains a high level of integrity. In comparison to other farms in its vicinity, it reveals its importance as a more prosperous farm largely through the architectural detail of the farmhouse. There are fewer brick buildings in this region than in other areas (such as Emmitsburg). Compared to the others, the Harbaugh-Willard Farm appears to have sustained fewer alterations and changes to the main house thus retaining a higher or equal level of integrity. Its agricultural and domestic outbuildings date from the early twentieth century and do not contribute significantly to the resource. Other brick houses with outbuildings more closely associated with the main house may elevate integrity.

The area known as Harbaugh's Valley was originally a Swiss settlement. One of the first settlers was George Harbaugh, a Swiss, who entered the region from Pennsylvania. The Swiss were probably attracted to the familiar landscape of the mountains. The Harbaughs, as a family, grew and prospered, and many Harbaughs still reside in the area to present day. The Harbaugh-Willard Farm was probably constructed by 1930. In 1958, it was owned by J. Harbaugh; in 1873, T. Williar resided there. The Willard family purchased the property in 1937 and have farmed it since that time.

Architecturally, the house shows elements of the transitional period between the Federal and Greek Revival styles particularly with the entrance treatment and the flemish bond brickwork. These stylistic elements were incorporated into the vernacular form that was developing in the region: the 2 story dwelling with a 2 story rear addition. While similar in form to its neighbors, stylistic details elevated the Harbaugh-Willard Farm.







F-6-52 Harbough-Willard Farm Sabillesville Road Salsillasville Frederick Country Photo: Many K Shyre March 1991 Ney loc: Manyland thistorical Trist
Annagalis MD West Elevation

4



F-6-52
Havbargh-Luilland Farm
Sabillasville Road
Sabillasville
Frederick Country
Photo: Mary & Shyre
April 1991
Neg. Loc: Maryland Historical Trist
Anneyclis MD
Sast Elevation



F-6-52 Harbauch-Willard Farm Sabillasville Road Salillasville Frederick County Photo: Mary K Shye April 1991 Neg. Loc: Manyland Historical Trist Annagolis MD Barn-north elevation



Harbaugh-Willard Farm Sabillasulle Kond Sabillasville Frederick County Photos Many K Shype April 1991 Neg. Loc: Manyland thesterical Trist Annoydis MD Odagenal chaten coop